



Mat Slab. (Heavily Reinforced)

SUPERSTOP

Paraseal LG (HDPE Side Up,  
Permanent Tape at 3" (8cm) Seams.

Polyethylene Base Sheet.

Mud Slab.

TREMDrain.

Unexcavated Earth.

Note: Paraseal Products require a minimum 24 psf compaction/ confinement to be effective.

Note: TREMDrain position may vary depending on placement of drains in Mat Slab.

Mat Slab with Mud Slab - System D (Also See BSOG-04).

No.	Date	Description	By

**TREMCO.** 3736 Green Road, Beachwood, Ohio 44122 216-292-8000  
 Project: **Below Slab-On-Grade**

Drawn by: W. Hensley	Scale: Not To Scale	Date: 04/19/05	Drawing/Order No: BSOG-08
----------------------	---------------------	----------------	---------------------------