

- 1. THIS DETAIL ALLOWS THE OPENING TO BE COMPLETED BEFORE THE STACK IS PLACED.
- 2. THE CLEARANCE NECESSARY BETWEEN THE OPTIONAL INSULATION AND METAL LINER AND THE STACK WILL DEPEND ON THE TEMPERATURE OF THE MATERIAL HANDLED BY THE STACK.
- 3. PRIMING OF THE SUBSTRATE MAY BE REQUIRED. FOLLOW SPECIFICATIONS AND MANUFACTURER'S RECOMMENDATIONS.



SHEET TITLE: SHEET METAL STACK VENT [HOT OR COLD] FULLY REINFORCED OVER CONCRETE SCALE: NTS

DRAWING	No.:		
DWG	NO.	LA-CF	FR-18

2023